



INSPECTIONS

YOU MUST CALL FOR INSPECTIONS FOR ALL ITEMS TICKED

This consent application has been approved subject to the following conditions:

1. Notice of at least one working day to be given prior to the following work being carried out:
 - (a) **Pouring concrete in -**

foundations	<input type="checkbox"/>
ground floor slab	<input type="checkbox"/>
suspended floor slab	<input type="checkbox"/>
bond beams	<input type="checkbox"/>
_____	<input type="checkbox"/>
 - (b) Installation of wooden flooring (ground floor) ☐
2. Notice of at least one working day to be given to enable inspection of the following items:
 - (a) **Pre-lining inspection including -**

braces	<input type="checkbox"/>
insulation - walls and ceiling	<input type="checkbox"/>
plumbing pipes	<input checked="" type="checkbox"/>
pressure testing of water piping	<input checked="" type="checkbox"/>
fireplaces and solid fuel heaters	<input type="checkbox"/>
_____	<input type="checkbox"/>
 - (b) **Drainage -**

foul water	<input type="checkbox"/>
stormwater	<input type="checkbox"/>
drainage testing	<input checked="" type="checkbox"/>
 - (c) **Final when job completed** ☒
3. Consent number is to be quoted when an inspection is requested.
4. THE APPROVED COPY OF PLANS AND SPECIFICATIONS TO BE ON SITE AT ALLTIMES WHEN THE INSPECTOR CALLS.
5. Keep dogs tied up when Inspector calls please.

IMPORTANT: ADVISE THE COUNCIL WHEN PROJECT IS COMPLETE

HAYTER
7 Nettlingham Pl.
TE PUKE

SPECIFICATIONS

1. Replacement of one of two 2012mm X 1240mm metal doors
in basement exterior blockwork with fixed wall
Materials: 100x50 framing dyna bolted to existing blockwork.
Exterior sheathing 6mm Hardiflex.
Installation in framing of window 630 X 1000.
2. Internal Partition 75x50 framing
Hardboard linings painted with Gloss Enamel.
Dyna bolted to concrete floor.
3. Installation Toilet, Shower + Vanity.