

45 Joanne Cres Street Lot ..... 39 ..... DPS ..... 17385 ..... Section ..... Block .....

**ROTORUA DISTRICT COUNCIL**

Drainage to sewer (7198)



BC

Owner: N. Hayes

Valuation No.: 655/947

Plumber:

Permit No.: 7257

Drainlayer: Morris & Breen

Appn. No.: 4429

**INSPECTIONS**

Date: 21/3/83

Date

22-3-83

*Diam Test pvc old section checked & tested*



Bill Coleman

Application No. 4429.

## ROTORUA DISTRICT COUNCIL

Valuation No. 655/947

### APPLICATION FOR PERMIT TO CARRY OUT SANITARY PLUMBING AND DRAINAGE WORK

I, the undersigned, hereby apply for permission to have the work described herein, and set out on the plans attached hereto, carried out in accordance with the provisions of the Drainage and Plumbing Regulations 1978 and Amendments at premises situated at:

Address 45 Joanne Cres. ROTORUA

#### Legal Description:

Lot No. 39 Deposited Plan No. 17385

Section No. Block No.

Description of Work: Connect drain age to Council Sewer.

Name and address of person for whom work is to be carried out:

Mrs. N. W. Hayes Te Weta Rd. Waikite Valley RD1

Name and address of Craftsman Plumber:

Name and address of Registered Drainlayer:

P.P. NORRIS & BREEN LTD.

Box 596

	Value	Fees
Plumbing	\$ :	\$ :
Drainage	\$ 36 :	\$ 15 :
<b>TOTAL FEES</b>		\$ 15 :

Signature:

Handwritten signature

Date:

21/3/83

#### FOR OFFICE USE ONLY

Receipt Number

14348

Fee Paid

15-00

Date Paid

21-3-83

Issue Approved

Handwritten signature

Date Approved

21-3-83

Permit No.

7257

See reverse for Fees and Notes

FOR OFFICE USE ONLY

# **FEES PAYABLE ON THE ISSUE OF ANY PLUMBING OR DRAINAGE PERMIT**

## **according to the Estimated Value of Work**

Value of work (excluding value of fittings)		
Value of Work		Permit Fee
Up to \$50		\$15
\$51 - \$100		\$20
\$101 - \$200		\$32
\$201 - \$300		\$38
\$301 - \$400		\$44
\$401 - \$500		\$50
\$501 - \$600		\$56
\$601 - \$700		\$62
\$701 - \$800		\$68
\$801 - \$900		\$75
\$901 - \$1000		\$80

\$1001 and over, \$7 extra for every \$200 or part thereof in excess of \$1000

### **IMPORTANT**

#### **INSPECTION AND TESTING REQUIREMENTS**

**DRAINAGE WORK:** Drainlayers are required to notify the Plumbing and Drainage Inspector when all work is completed. This includes effluent disposal systems for septic tanks. All drains will be tested with a 1.5 m head of water. To implement this test it will be necessary for persons undertaking drainage work to have sufficient drain plugs to fill all sections of the drain prior to the Plumbing and Drainage Inspector arriving on the job, also to have available a stand pipe to apply the 1.5 m head pressure.

This form of testing is essential to exclude the possibility of ground water infiltration with its attendant increase in pumping charges and overloading of the sewers and treatment plant.

**PLUMBING WORK:** Plumbers are required to notify the Plumbing and Drainage Inspector when work is ready for inspection as follows:

- (a) When the building has been initially piped out and wastes are installed (before wall linings are fixed and floors laid).
- (b) When work is complete.

#### **Plans of Drainage and Plumbing Work**

In the case of single houses a preliminary drainage plan will not be required. In all other cases, however, plans of the preliminary proposal are to be submitted at the time of application for a permit. In all instances, however, an "as laid" plan must be available on site as a prerequisite to a test of the work.

In commercial buildings full plans and elevations of plumbing stacks must be provided at the time of application for a permit.