

22 August 2007

File Ref: ~~63-05-026-05~~
Your Ref: 175781-R-P-C022

Doc No: OW-89171
Enquiries to: Joanne Watts



MTEC Consultants Ltd
PO Box 878
ROTORUA

fixed to MTEC.
23/8/07 2.5
J
copy to: ~~P32160 P32245~~
P32223

Attention: Richard Lawton

Dear Richard,

**NOTICE OF DECISION REGARDING VARIATION TO APPROVED
SUBDIVISION CONSENT**

Consent No.: 63 05 026
Applicant: Pioneer Property Trust Ltd
Location of proposal: Western Road
Legal Description: Lot 17 DP 336769 and easement over Lot 16 DP 336769
Proposal: Proposed amendment to extend Pioneer Rd to allow access for future development, the vesting of Lot 31 in RDC as Drainage reserve, consequential changes including the removal of easements and rearrangement of lots.

I wish to advise that the following decision has been made under authority delegated to staff in respect of the above application:

(a) Decision regarding non notification of the application

That pursuant to Section 93(1)(b) of the Resource Management Act 1991, the Rotorua District Council resolves that the adverse effects of the proposed change of conditions of consent will be minor and the application need not be notified. The Council is satisfied after taking into due consideration the requirements of Section 94, 94A(a) 94B & C and Section 127(4) that in the opinion of Council no persons are considered adversely affected by the change of conditions. Council is also satisfied that no special circumstances exist that require notification of the consent application in accordance with Section 94C(2) of the Resource Management Act 1991.

(b) Decision on the application

That pursuant to Sections 34A, 104, 108 and 127 of the Resource Management Act 1991, the Rotorua District Council resolves to grant consent to change the original subdivision consent granted on 13 February 2006 and varied on 3 July 2007. The applicant is Pioneer Property Trust Ltd and the consent allows for the subdivision of the property at Western Road legally described as Lot 17 DP 336769 into 86 residential lots, 2 local purpose reserves, 2 new roads to vest in RDC, two access lots and a balance lot.

For completeness, the original conditions of consent are reproduced below with changes to the original conditions resulting from this decision shown in italics. The consent is now subject to the following conditions:

Stage 1 comprises Lots 1-14, 17-23 and the balance lot.

Stage 2 comprises Lots 15, 16, 64-87, 91 & 93 and the balance lot.

Stage 3 comprises Lots 24 – 63, 88, 90, 92 & 94

GENERAL CONDITIONS THAT APPLY TO ALL STAGES

1. That all engineering works required to be undertaken to satisfy the conditions of this consent shall be carried out in accordance with the Rotorua Civil Engineering Industry Standard (RCEIS) and the District Plan, to the satisfaction of the District Engineer.
2. That all land to vest in Council, roads, street lighting, sewerage, stormwater, water supply, telecommunications, electricity facilities shall be provided to the standards required by Council as a service operator or other service operators in which the infrastructure will be vested. Certification from Council or other appropriate service operator that it is satisfied with the standard of the service provided, and that it will accept the particular service, shall be provided to Council as consent authority before it issues any Section 224 Certificates to enable a survey plan to be deposited. Those services certified for approval by Council as service operator shall vest in Council on deposit of the survey plan.
3. That engineering design plans shall be submitted to all relevant services operators for written approval before commencing construction work. Work undertaken without Council's written approval for those services to vest in Council, shall not be accepted.
4. That in carrying out the proposed works no run off, silt, sediment or other materials shall be permitted to discharge off-site that could damage or disturb neighbouring properties, public roads or drains by installing and maintaining appropriate erosion and sediment controls, prior to and during the works, and until the site is stabilised.
5. That all filling shall be certified by a Chartered Professional Engineer.

STAGE 1

6. That the Land Transfer Plan be prepared in accordance with the preliminary plan of subdivision prepared by MTEC Consultants Ltd, numbered 175781-R-P-D002, Sheet number 01 Issue E and dated 22/11/05 in so far as it relates to Stage 1 - Lots 1-14, 17-23 and the balance lot.

Financial Contribution

7. That a financial contribution of \$ 47 400 (GST inclusive) for reserves and heritage purposes be paid to Council. This amount has been assessed at 5% of the land value of proposed Lots 1 -14 and Lots 17 – 23. Where lots have an area over 900m² the value of an 850m² house site on each of the lots has been assessed.
8. That a footpath and kerb and channel shall be constructed in accordance with RCEIS, along the Western Road frontage. Rotorua District Council will contribute the agreed sum of \$18,341.00 (excl. GST) on completion.
9. That overland flow paths shall be identified and shown as easements in favour of Council.

10. That for Lots 1 – 14 and 17 - 23 there shall be, 1 (one) only vehicle crossing per Lot, on-site parking and turning for each household unit shall be provided, and all egress from these Lots shall be in a forward movement. That the owners and future owners of Lots 1 – 12 are advised that the areas inside the overland flow easement are low lying with the potential to act as secondary flow paths for short durations during extreme storm events. Earthworks, access formation and landscaping within the Lots shall not restrict the overland flows or divert water on to adjacent Lots.
11. The owners and future owners of the relevant Lots are advised of conditions 10 - 11 way of a Consent Notice registered on the relevant Certificates of Title.
12. Any proposed landscaping of the proposed reserve shall be undertaken in accordance with an approved landscaping plan. Approval must be obtained to the satisfaction of the Director, Community Services prior to any landscaping works commencing.

STAGE 2

13. That the Land Transfer Plan be prepared in accordance with the preliminary plan of subdivision prepared by MTEC Consultants Ltd, numbered 175781-R-P-D002, Sheet number 01 Issue F and dated 05/06/07 in so far as it relates to Stage 2 - Lots 15, 16, 64-87, 91 & 93 and the balance lot.

Financial Contribution

14. That a financial contribution of \$ 56,900 (GST inclusive) for reserves and heritage purposes be paid to Council. This amount has been assessed at 5% of the land value of proposed Lots 15, 16 64-86. Where lots have an area over 900m² the value of an 850m² house site on each of the lots has been used.
15. Deleted (see variation 3 July 2007)

Amalgamation condition

16. That Lot 91 hereon (Legal Access) be held as to two undivided one half shares by the owners of Lots 15 & 16 hereon as tenants in common in the said shares and that individual Certificates of Title be issued in accordance therewith.

Street naming

17. That proposed street names for both proposed roads be forwarded to Council for consideration, that consultation be undertaken with emergency services and that the street name receive approval by Council prior to requesting Section 223 certification.
18. That Lots 84, 85 and 86 shall have building platforms at or above the Environment Bay of Plenty 1% AEP flood level of 285.30 metres Moturiki Datum.
19. That the overland flow paths are identified and shown as easements in favour of Council.
20. That the owners and future owners of Lots 84, 85 and 86 are advised that the areas outside of the building platforms are low lying with the potential to act as secondary flowpaths for short durations during extreme storm events. Earthworks, access formation and landscaping within the lots should not restrict the natural overland flows or divert water onto adjacent lots.
21. That the owners and future owners of Lots 15, 16, 65 - 69 are advised that the areas inside the overland flow easement are low lying with the potential to act as secondary flow paths for short durations during extreme storm events. Earthworks, access formation and

landscaping within the Lots shall not restrict the overland flows or divert water on to adjacent Lots.

22. That any proposed building on Lots requiring a Building Consent outside of the certified building platforms will require the construction of a building platform at or above the Environment BOP 1% AEP flood level. The building platform shall be certified as suitable for the building by a suitably experience and qualified Chartered Professional (Soils) Engineer.
23. The owners and future owners of the relevant Lots are advised of conditions 21 - 23 way of a Consent Notice registered on the relevant Certificates of Title.
24. That Lots 87 and 93 be vested in Council. That the type of reserve shown on the LT plan be to the satisfaction of the Director of Community Services.
25. That Lot 93 shall vest in Council as road.

STAGE 3

26. That the Land Transfer Plan be prepared in accordance with the preliminary plan of subdivision prepared by MTEC Consultants Ltd, numbered 175781-R-P-D002, Sheet number 01 Issue G and dated 27/07/07 in so far as it relates to Stage 3 - Lots 24 – 63, 88, 90, 92 & 94 *unless amended by conditions of this consent.*

Financial Contribution

27. That a financial contribution of \$ 57,050 (GST inclusive) for reserves and heritage purposes be paid to Council. This amount has been assessed at 5% of the land value of proposed Lots 24 – 30, 32 -35 and Lots 51 - 63. Where lots have an area over 900m² the value of an 850m² house site on each of the lots has been used.
28. In addition to the above financial contribution, a further financial contribution for reserve and heritage purposes shall be calculated at 5% of the land value of proposed Lots 36 – 50 (being those lots added or changed in area from the original scheme plan) and that this sum be paid to Council. Where lots have an area over 900m² the value of an 850m² house site on each of the lots will be used.
29. The contributions payable may be satisfied by transferring the title of Lot 88 to Council, provision of all agreed works (refer advice note), and the payment of any cash difference between the value of these two items and the calculated contribution.

Amalgamation condition

30. That Lot 90 hereon (Legal Access) be held as to six undivided one sixth shares by the owners of Lots 56, 57, 58, 58, 59 60 & 61 hereon as tenants in common in the said shares and that individual Certificates of Title be issued in accordance therewith.
31. All steep slopes unsuitable for building shall be shown on Land Transfer Plan as areas restricted from building prior to application for Section 223. A consent notice clause shall set out restrictions applicable within the area to the satisfaction of the District Engineer.
32. That stormwater over land flow paths for Lots on the northern slope shall be identified and protected by easements on the Land Transfer Plan prior to application for Section 223.
33. That the owners and future owners of Lot 58 and the affected Lots on the northern slope shall be advised that the areas inside the overland flow easement are low lying with the potential to act as secondary flow paths for short durations during extreme storm events. Earthworks, access formation and landscaping within the Lots shall not restrict the overland flows or divert water on to adjacent Lots.

34. *Deleted*
35. That a 100 mm ϕ watermain shall be installed between the proposed Road (Lot 92) and Kingsley Drive. The watermain be protected by either a Utility Reserve or easement whichever is agreed to by Council's water asset manager.
36. That Lot 89 & 92 be vested in Council as Road.
37. That the owners and future owners of the affected Lots are advised that the areas outside of the building platforms are low lying with the potential to act as secondary flowpaths for short durations during extreme storm events. Earthworks, access formation and landscaping within the lots should not restrict the natural overland flows or divert water onto adjacent lots.
38. *Deleted*
39. That the Lots 56 - 61 shall be restricted to one household unit and no subsidiary household unit.
- 39a. The owners and future owners of the relevant Lots are advised of conditions –37 & 39 by way of a Consent Notice registered on the relevant Certificates of Titles:
40. That the overland flow paths are identified and shown as easements in favour of Council.
41. That Lot 31 *shall vest in Council as Drainage Reserve and shall be constructed to contain the flows from a 1% AEP storm event.*
42. That drainage works set out in the MTEC Consultants letter of 24 May 2005 be undertaken to improve the drainage of the proposed reserve at the applicant cost. In addition that a building platform on or above EBOP's 1% AEP flood level of no less than 400m² be provided in an agreed location suitable for the purpose of construction of playground equipment.
43. That condition 2 be met in so far as it relates to Lot 88 & that Lot 88 be vested in Council within 12 months of the granting of the variation *approved on 3 July 2007*. That the type of reserve shown on the LT plan be to the satisfaction of the Director of Community Services.

The reasons for the decision are:

1. The Council is satisfied that there will be no more than a minor adverse effect resulting from the modification of the original consent as proposed which proposes:
 - the road to be extended to provide access for future Stage 4 to Pioneer Rd instead of to Hall Rd via the land to the east of this subdivision;
 - removes the need for overland flowpath easements; and
 - confirms that Lot 31 will be vested in Council as Drainage Reserve.
2. Additional earthworks proposed will allow the construction of the road up the steep slope to the upper level of the development. Stage 4 will be the subject of a subdivision consent. The draft layout for future development - Stage 4 shows that a turning head can be provided. In approving this variation it has been noted that an application for consent for earthworks and stormwater discharge has been lodged with EBOP.
3. The proposed layout for future Stage 4 also shows that the watermain link through to Kingsley Dr and the boundary of the Everard Block can be provided.

4. **The removal of the overland flow path through Lot 30 and the provision of Lot 31 as a separate Drainage lot allows the lot to be designed to contain overland flows from significant storm event.**
5. **The change of conditions is considered to be consistent with the relevant objectives & policies of the District Plan and the purposes and principles of the Resource Management Act 1991.**
6. **No persons were considered affected by the original consent or the variation. Council has reconsidered whether there are any parties affected by this variation to the consent and confirmed there are no parties considered affected. In this regard it is noted that no persons from Kinsley Dr are considered affected by this variation. It will result in further earthworks in the vicinity of the proposed road but these will be the subject of an EBOP consent for which affected parties will be considered. Vesting of Lot 31 as Drainage Reserve will have a positive effect on the landowner to the west of the subdivision as it will allow effective on drainage of overland flow from the catchment to the west of the subdivision, through the subdivision and to the Ngongotaha Stream.**

The applicants are advised of the following in relation to the variation:

(a) Financial contribution

The financial contribution payable has been reduced by \$2300 being 5% of the land value of Lot 31 which is now to vest in Council as Drainage reserve.

Engineering advice

- (b) Lot 31 is to be shaped and provided with a concrete base (channel) and finished to a mowable standard.
- (c) A turning head at the end of the road is not required for this stage of development as turning is provided by the loop road.

(d) Right of objection to this decision

If you are dissatisfied with any aspect of the decision, you have a right of objection to Council under section 357 of the Resource Management Act 1991. In the case of a decision regarding an application to change consent conditions of the original consent, such as this, any objection is limited in scope to objecting against the conditions that were changed or cancelled rather than revisiting original consent conditions. Please advise Council in writing stating the reasons for the objection and the preferred outcome within 15 working days of receiving this decision. If no objection is received it will be assumed that the applicant accepts this decision.

(e) Timeframe for giving effect to this consent

This subdivision consent lapses on the expiry of 5 years after the date of commencement of the consent unless the consent is 'given effect' to. The commencement date in the case of this non notified consent is the date of receiving the original decision letter NOT the date of receiving the decision letter for this variation. (Sect 116). A subdivision is deemed to be 'given effect to' when the survey plan in respect of the subdivision has been submitted to Council under Section 223. Certification that all conditions of the subdivision consent have been complied pursuant to Section 224 must be obtained by the applicant within a period of less than 3 years from the date the survey plan was approved.

For completeness the reasons & advice notes for the original decision (where relevant) were that:

1. The site is zoned Residential B in the District Plan where the proposed subdivision is a Controlled Activity. As a controlled activity as it fully complies with the Rules for subdivision in 16.3 and 16.4 of the District Plan.
2. After considering the assessment criteria for Controlled activity subdivision Council is satisfied that any adverse effects of the proposal are minor, or can be remedied or mitigated by the proposed works and conditions of consent. The subdivision is also considered to be consistent with the relevant objectives & policies of the District Plan and the purposes and principles of the Resource Management Act 1991.
3. It is noted that significant engineering works have been proposed as part of this subdivision to ensure that site limitations in terms of both overland flow and inundation from the Ngongotaha Stream in extreme storm events issues and also in terms of soil suitability for building have been adequately addressed. Sufficient provision has been made to ensure potential inundation of the house sites from the Ngongotaha Stream can be avoided. Large scale earthwork are proposed and required to ensure all proposed building platforms are above the 1% AEP storm event. Certification of buildings sites will be required to ensure each building site is suitable for building.
4. No persons are considered adversely affected by this subdivision proposal. It is noted that the adjoining landowners downstream of the property to the east were considered affected parties by EBOP in terms of the stormwater discharge consent as there is a ponding effect on the property to the east of proposed Lot 87 in storm events.
5. A financial contribution is payable in accordance with Appendix U of the District Plan towards the development of existing, and purchase of additional land to enhance the amenity and heritage value of reserves. In this case Council have accepted the vesting of Lot 88 as part payment of the reserve contribution. A neighbourhood park is not essential in this area but is desirable to provide play opportunities for children close to home. The land being offered is compromised by poor drainage and soil structure, but will have some recreation and amenity value if properly developed.

The applicants are advised that:

(f) Obligations under the Historic Places Act 1993

Council has no records of an archaeological site on this property. This may be due to one of two factors. Either, there are no sites present or there has not been an archaeological survey undertaken. Please be advised that both known and unknown archaeological sites are protected under the Historic Places Act 1993. If during the exercising of this consent any archaeological site is uncovered work must stop and permission be obtained from the Historic Places Trust under the provisions of either Section 11 or 12 of the Historic Places Act 1993.

(g) Financial contribution

With regard to payment of the financial contribution for reserves and heritage purposes, the applicant has requested Council consider some credit for the recreation value of Lot 88 (proposed Local Purpose Reserve (Drainage / Recreation)). Lot 88 has been valued at \$15,000 including GST excluding all site improvement works. A neighbourhood park is needed in the area.

Works credited against the reserves contribution payable can include the landscaping of the reserve such as the cost of trees, footpath etc & the creation of the building platform required by condition 17 but should exclude the value of works needed to dispose of topsoil from the subdivision and drainage required for stormwater disposal from the subdivision.

Any proposed works will need to be agreed to by Council's Parks & Recreation Dept prior to being undertaken.

(h) Engineering advice

The earthworks required for construction of the development must comply with the permitted activity conditions of Environment Bay of Plenty's Land & Water Plan or a Resource Consent will be required.

Prior to any works in the road reserve, a Road Opening Notice must be obtained from Council. This is available free of charge, by contacting Tiki Galvin on Ext 8238.


The Building platforms are to be construction for 1% AEP storm event as the site will be affected by the Ngongotaha Stream.

If you have any questions regarding this consent, please contact Joanne Watts, Best Practise Advisor or the Duty Planner.

Yours faithfully



Nigel Wharton
Director, Environmental Services



MEMORANDUM OF PROPOSED EASEMENTS			
PROPOSED EASEMENT	PROPOSED EASEMENT	PROPOSED EASEMENT	PROPOSED EASEMENT
1. EASEMENT OF WAY	2. EASEMENT OF WAY	3. EASEMENT OF WAY	4. EASEMENT OF WAY
5. EASEMENT OF WAY	6. EASEMENT OF WAY	7. EASEMENT OF WAY	8. EASEMENT OF WAY
9. EASEMENT OF WAY	10. EASEMENT OF WAY	11. EASEMENT OF WAY	12. EASEMENT OF WAY
13. EASEMENT OF WAY	14. EASEMENT OF WAY	15. EASEMENT OF WAY	16. EASEMENT OF WAY
17. EASEMENT OF WAY	18. EASEMENT OF WAY	19. EASEMENT OF WAY	20. EASEMENT OF WAY
21. EASEMENT OF WAY	22. EASEMENT OF WAY	23. EASEMENT OF WAY	24. EASEMENT OF WAY
25. EASEMENT OF WAY	26. EASEMENT OF WAY	27. EASEMENT OF WAY	28. EASEMENT OF WAY
29. EASEMENT OF WAY	30. EASEMENT OF WAY	31. EASEMENT OF WAY	32. EASEMENT OF WAY
33. EASEMENT OF WAY	34. EASEMENT OF WAY	35. EASEMENT OF WAY	36. EASEMENT OF WAY
37. EASEMENT OF WAY	38. EASEMENT OF WAY	39. EASEMENT OF WAY	40. EASEMENT OF WAY
41. EASEMENT OF WAY	42. EASEMENT OF WAY	43. EASEMENT OF WAY	44. EASEMENT OF WAY
45. EASEMENT OF WAY	46. EASEMENT OF WAY	47. EASEMENT OF WAY	48. EASEMENT OF WAY
49. EASEMENT OF WAY	50. EASEMENT OF WAY	51. EASEMENT OF WAY	52. EASEMENT OF WAY
53. EASEMENT OF WAY	54. EASEMENT OF WAY	55. EASEMENT OF WAY	56. EASEMENT OF WAY
57. EASEMENT OF WAY	58. EASEMENT OF WAY	59. EASEMENT OF WAY	60. EASEMENT OF WAY
61. EASEMENT OF WAY	62. EASEMENT OF WAY	63. EASEMENT OF WAY	64. EASEMENT OF WAY
65. EASEMENT OF WAY	66. EASEMENT OF WAY	67. EASEMENT OF WAY	68. EASEMENT OF WAY
69. EASEMENT OF WAY	70. EASEMENT OF WAY	71. EASEMENT OF WAY	72. EASEMENT OF WAY
73. EASEMENT OF WAY	74. EASEMENT OF WAY	75. EASEMENT OF WAY	76. EASEMENT OF WAY
77. EASEMENT OF WAY	78. EASEMENT OF WAY	79. EASEMENT OF WAY	80. EASEMENT OF WAY
81. EASEMENT OF WAY	82. EASEMENT OF WAY	83. EASEMENT OF WAY	84. EASEMENT OF WAY
85. EASEMENT OF WAY	86. EASEMENT OF WAY	87. EASEMENT OF WAY	88. EASEMENT OF WAY
89. EASEMENT OF WAY	90. EASEMENT OF WAY	91. EASEMENT OF WAY	92. EASEMENT OF WAY
93. EASEMENT OF WAY	94. EASEMENT OF WAY	95. EASEMENT OF WAY	96. EASEMENT OF WAY
97. EASEMENT OF WAY	98. EASEMENT OF WAY	99. EASEMENT OF WAY	100. EASEMENT OF WAY
COPYRIGHT - MTEC CONSULTANTS			
SERVICES			
DRAWN: SA/M DESIGNED: LCM			
CHECKED: LSM SURVEYED BY:			
LOCAL AUTHORITY REF: RDC REF 63-05-025			
SURVEYORS ENGINEERS PLANNERS			
PIONEER PROPERTY TRUST LTD			
PROJECT LOCATION: WESTERN ROAD NGONGOTAHA			
PROPOSED SUBDIVISION OF LOT 17 DP 336769 SCHEME PLAN			
SCALE: 1:1000			
DRAWING NO: 175781-R-P-D002			
SHEET NO: 01			
ISSUE: G			