TCC588399

WAIHI ROAD.

146° 05'

40.24

DRIVEWAY

No 242

56° 05'

20.12

EXIST HOUSE (APPROX POSN)

N

LOT 8
DP 32966.
VALN 06699/180-00

MH 145

ASSUMED DATUM L.L. = 100.00
L.L. 100.000 (Depth 1.791)
INV - 98.209

8.00m

CONNECT TO EXISTING INSPECTION BEND TO SUIT.

1.5m

S.H.

DP

PROPOSED MH.

90

SEWER

PROPOSED HOUSE SITE

20.12

PROPOSED REALIGNMENT OF SEWER

150 ø

PROPOSED SEWER DIVERSION

EXISTING 23

Grade 0.444 1:225

PROPOSED MH.

1.5m

CONNECT TO EXIST (INSPECTION BEND TO SUIT.)

NOTE: No RECORDS OF SEWER GRADIENT WITHIN COUNCIL ARCHIVES.

MH 146

ASSUMED DATUM
L.L. 99.775
INV.L. 98.653
Depth 1.122m

| | | | |
|---|---|---|---|
| **HARBOUR HOMES**<br>Box 8011 Cherrywood, 07 5786864<br>GST No. 58-914-798 | PROPOSED DWELLING FOR<br>MR & MRS P & K MITCHELL<br>AT 242 WAIHI RD. TAURANGA | SITE PLAN. | SCALE:- 1:100. |